DESIGN REVIEW BOARD Monday September 29, 2025 7:30 p.m.

Virtual Meeting using Zoom

Meeting ID: 837 5422 1747 (Instructions for accessing below)

Under Governor Baker's Act "Extending Certain COVID-10 Measures Adopted During the State of Emergency", extending the "Executive Order Suspending Certain Provisions of the Open Meeting Law G.L. c. 30A, S20,", issued June 16, 2021, and extended several times again through 2027, meeting of public bodies could be conducted virtually provided that adequate access is provided to the public.

To view and participate in this virtual meeting on your phone, download the "Zoom Cloud Meetings" app in any app store or at www.zoom.us. At the above date and time, click on "Join a Meeting" and enter the following Meeting ID: 837 5422 1747 Link: https://us02web.zoom.us/j/8375422 1747

To view and participate in this virtual meeting on your computer, at the above date and time, go to www.zoom.us click "Join a Meeting" and enter the following ID: 837 5422 1747

HEARINGS:

Public notice is hereby given that EP 63 Kendrick Realty, LLC has made application to the Design Review Board for a Special Permit pursuant to the Sign By-Law Section 5.4.2.2(e) for a sign above the roof line of a building for two building mounted signs, one at the front and one at the rear of the building; Section 5.5.3.1(a) for more than one freestanding sign on a parcel; Section 5.4.2.2(f) for two monument signs within the required setback and within 15' of the street line; Section 5.5.3.3(b) for two monument signs in excess of three feet height; Section 5.5.3.3(c) for two freestanding signs, with more than one support; and Section 5.5.1(a) for more than one sign indicating the number of the building, and any other applicable sections of the By-law.

APPLICANTS:

Brett Doyle, Doyle And Mattheson, Inc. applying for exterior alterations for ADA compliant ramp to the building entrance at 87 Chestnut Street.

REVIEW

Minutes of 9/8/2025 meeting.

Next Public Meeting – October 20, 2025 at 7:30pm

GEORGE GIUNTA, JR.

ATTORNEY AT LAW* P.O. Box 70

WEYMOUTH, MASSACHUSETTS 02190

*Also admitted in Maryland EMAIL: george.giuntajr@needhamlaw.net

TELEPHONE (781) 449-4520

FAX (781) 465-6095

August 29, 2025

Elisa Lichtman Town of Needham Office of Planning and Community Development 500 Dedham Avenue, Suite 118 Needham, MA 02492

Via Email: elitchman@needhamma.gov

Re: EP 63 Kendrick Realty, LLC

63 Kendrick Street Sign Special Permits

Dear Elisa,

Please be advised that this office represents EP 63 Kendrick Realty, LLC (hereinafter, "Kendrick Realty") owner of the property currently known and numbered 63 Kendrick Street, f/k/a 155 Fourth Avenue (the "Premises"). In connection therewith, submitted herewith for consideration by the Design Review Board, please find the following:

- 1. Application to install lit channel number sign (sign S1 front of building);
- 2. Application to install lit channel number sign (sign S2 rear of building);
- 3. Application to install single-sided, non-illuminated monument sign (sign S3 loading entrance);
- 4. Application to install single-sided, non-illuminated monument sign (sign S4 rear entrance);
- 5. Plan set prepared by SignWorks Group", dated 8/25/25, consisting of sheets as follows: (a) Sheet M1, "Sign Location Plan; (b) Sheet "Sign", depicting sign S1 as designated on the Sign Location Plan; (c) Sheet "Sign", depicting sign S2 as designated on the Sign Location Plan; (d) Sheet "Sign Sign", depicting signs S3 and S4 as designated on the Sign Location Plan; and (e) eight (8) renderings, unlabeled;
- 6. Site Plan, prepared by STA Design, dated 8/28/2025; and
- 7. Collection of Google Street View photos depicting the exterior view of the Premises over time.

The Premises is situated in the New England Business Center Zoning District (the "NEBC") and is bounded by streets on two sides; Kendrick Street to the front and Fourth Avenue to the side. The Premises consists of contains approximately 261,361 square feet of area, with approximately

372.99 feet of frontage on Kendrick Street and approximately 739.89 of frontage on Fourth Avenue. The Premises is currently fully developed, and is occupied by an existing commercial building (the "Building") and associated parking, loading and driveway areas, as permitted and constructed pursuant to Site Plan Special Permit Decision, Application #97-8, filed with the Town Clerk on August 8, 1997, filed with the Norfolk County Registry District of the Land Court as Document No. 771815, as affected by Site Plan Special Permit Amendment Decision, dated March 17, 1998, filed with said Registry District as Document No. 822218. A redevelopment and renovation of the Premises was recently approved by the Planning Board, as set forth in Amendment to Decision dated January 4, 2025, recorded with Norfolk County Registry District of the Land Court as Document No. 771815.

In connection with the contemplated redevelopment and renovation, a series of four signs are proposed: two building mounted, lit channel letter signs, one in the front and one in the rear of the building, and two non-illuminated monument signs on Fourth Avenue. For a variety of reasons, as set forth below, all four signs require special permits pursuant to the Needham Sign By-Law.

The building mounted channel letter signs are located in the approximate center of the front and rear of the building. Both signs state the street number of the building, i.e., "63" and are face lit. The sign on the front of the building has an outside measurement of 37" high x 58" wide, for an area of 14.90 square feet. The sign on the rear of the building has an outside measurement of 19" high x 28" wide, for an area of 3.69 square feet. As may be seen in the renderings, both signs project above the portion of the roof in which they are set. As a result, a special permit is or may be required from the provisions of Section 5.4.2.2(e) for both signs.¹

The Premises has two parking areas; a small area to the front, accessed from Kendrick Street, and a large area to the rear, accessed via two entrances off Fourth Avenue. The two freestanding, monument signs are proposed to be located at the two entrances to the rear parking area. Both of these signs have a measurement of 30" high x 18" wide, for an area of 3.75 square feet, and are set on top of a concrete base, measuring 18" high x 30" wide above grade, for a total structure height of 48" inches. Sign S3, located at the entrance closest to Kendrick Street, in the vicinity of the loading bay, will be oriented to align with the driveway entrance, will state the address of the Building (i.e., "63 Kendrick") and provide directional indicators for "Parking" and "Deliveries". Sign S4, located at the entrance furthest away from Kendrick Street, towards the rear of the parking area, will be oriented to be parallel to Fourth Avenue, will state the address of the Building (i.e., "63 Kendrick") and provide a directional indicator for "Parking".

Whereas the two monument signs constitute two freestanding signs, a special permit is required from the provisions of Section 5.5.3.1(a).³ Both monument signs will be located within the

¹ Section 5.4.2.2(e) provides that "No portion of any sign shall be located above the roof line of a building. Roof line means the intersection of the exterior wall and the roof."

² The concrete base for each sign will extend an additional 42" below grade.

³ Section 5.5.3.1(a) provides that "One permanent sign whether permanently attached or freestanding, as further described in Sub-sections 5.5.3.2 and 5.5.3.3 of this article, for each occupant of separate space per street that the premises abut. *However, no permit may be granted for more than one freestanding sign per parcel*" (emphasis added).

required setback area and within 15 feet of the street line. As a result, a special permit is required from the provisions of Section 5.4.2.2(f).⁴ In addition, because both signs are set on top of a concrete base, with a total height of four feet, they also require a special permit from the provisions of Section 5.5.3.3(b) for a monument sign exceeding 3 feet above street grade.⁵ And, because the two monument signs are freestanding signs with their own, independent support, they also require a special permit from the provisions of Section 5.5.3.3(c).⁶

Finally, in addition to the above relief, because all four proposed signs set forth the number of the building in a sign larger than two square feet, a special permit is or may also be required from the provisions of Section 5.5.1(a) for more than one sign indicating the number of the building.⁷

Kendrick Realty hereby requests that the aforementioned special permits issue and makes formal application therefor.

Please review and docket the foregoing for a hearing with the Design Review Board at the September 29, 2025 meeting. In connection therewith, please provide the requisite legal notice and abutter list for the special permit proceedings, so that my client and I may make timely publication and mail the notices.

Do not hesitate to let me know if you have any questions or require anything in connection with this request. As always, your courtesy and assistance are appreciated.

Sincerely,

George Giunta, Jr.


MM

⁴ Section 5.4.2.2(f) provides that "No freestanding sign shall be located within a required side or rear yard or within fifteen feet of a streetline or extend more than twenty feet above adjoining ground level."

⁵ Section 5.5.3.3(b) provides that "Every freestanding sign placed within thirty feet of the curb line of intersecting streets and driveways shall have an open space of at least seven feet from the ground to the base of the sign, except that *monument signs may be no more than 3 feet above street grade*" (emphasis added).

⁶ Section 5.5.3.3.(c) provides that "All freestanding signs on the same parcel of land shall be attached to the same support."

⁷ Section 5.5.1(a) provides that "One on-premise sign, either attached or free-standing, indicating only the name and/or profession of the owner or occupant, the street and/or number, not to exceed two square feet in area. No permit is required."



SIGN LOCATION PLAN

SWG

SignWorks Group

60 Arsenal Street Watertown, MA 02472 617 • 924 • 0292 fax 617 • 924 • 0279

CUSTOME

Edgewater Properties

PROJECT:

63 Kendrick

DATE:

08/25/2025

SCALE:

As Noted

DRAWN BY:

ΑE

WORK ORDER:

11337

DRAWING NO:

FILE:

REVISIONS:

This drawing is given in confidence and may not be used or disseminated in any way without prior written consent from this Company. All common law and copyright laws are hereby specifically reserved.






TOWN OF NEEDHAM

DESIGN REVIEW BOARD


Public Service Administration Building 500 Dedham Avenue Needham, MA 02492 **Application and Report**

Property Location: 63 Kendrick Street					
Owner:	EP 63 Kendrick Realty, LLC				
Address:	C/O Edgewater Properties, LLC 14 Mica Lane, Suite 202	Wellesley	MA	02481	
Telephone	Street . 781-552-4558 (Mitchell A. Kassler)	City	State	Zip	
Applicant:	EP 63 Kendrick Realty, LLC				
Address:	C/O Edgewater Properties, LLC 14 Mica Lane, Suite 202	Wellesley	MA	02481	
Telephone	Street · 781-552-4558 (Mitchell A. Kassler)	City	State	Zip	
Designer/I	nstaller: SignWorks Group				
Address:	60 Arsenal Street	Watertown	MA	02472	
Telephone	Type of Application Sign Minor Project Exterior Alterations Major Project (Site I preliminary final Flexible Subdivision Planned Residential Residential Compou	Plan Review) Development	State	Zip	
· ·	ption of sign or project: mounted, face lit, channel letter sig	n at front of building	, bearing the	street number	
of the bu	ilding. Sign is 14.90 square feet in	area and projects be	yond that po	ortion of the roof	
which it i	s mounted.				

Please email completed application to elitchman@needhamma.gov









SWC

SignWorks Group

60 Arsenal Street Watertown, MA 02472 617=924=0292 fax 617=924=0279

CLISTOME

Edgewater Properties

PROJECT:

63 Kendrick

DATE:

08/25/2025

SCALE:

As Noted

DRAWN BY:

ΑE

WORK ORDER:

11337

DRAWING NO:

FILE:

REVISIONS:

This drawing is given in confidence and may not be used or disseminated in any way without prior written consent from this Company. All common law and copyright laws are hereby specifically reserved.

SIGN 1








TOWN OF NEEDHAM

DESIGN REVIEW BOARD


Public Service Administration Building 500 Dedham Avenue Needham, MA 02492 **Application and Report**

Property L	Property Location: 63 Kendrick Street					
Owner:	EP 63 Kendri	ck Realty, LLC				
Address:	C/O Edgewate 14 Mica Lane,	r Properties, LLC Suite 202	Wellesley	MA	02481	
Telephone:	Street 781-552-4558 (N	litchell A. Kassler)	City	State	Zip	
Applicant:	EP 63 Kendri	ck Realty, LLC				
Address:	C/O Edgewate 14 Mica Lane,	r Properties, LLC Suite 202	Wellesley	MA	02481	
	Street 781-552-4558 (M	itchell A. Kassler)	City	State	Zip	
Address:	60 Arsenal Str		Watertown	MA	02472	
Designer/I	nstaller: SignV					
Address:	Street	eei	<i>V</i> vatertown City	State	Zip	
Telephone:	617-924-0292					
		Type of Application ☐ Sign ☐ Minor Project ☐ Exterior Alterations ☐ Major Project (Site ☐ - preliminary ☐ - final ☐ Flexible Subdivision ☐ Planned Residential ☐ Residential Component	Plan Review) Development			
	ption of sign or p mounted, face		ın at rear of building,	bearing the	street numbe	
of the bu	ilding. Sign is	3.69 square feet in a	rea and projects bey	ond that por	tion of the roc	
which it is	s mounted.					

Please email completed application to elitchman@needhamma.gov









SWC-

SignWorks Group

60 Arsenal Street Watertown, MA 02472 617 • 924 • 0292 fax 617 • 924 • 0279

CUSTOME

Edgewater Properties

PROJECT:

63 Kendrick

DATE:

08/25/2025

SCALE:

As Noted

DRAWN BY:

AE

WORK ORDER:

11337

DRAWING NO:

FILE:

REVISIONS:

This drawing is given in confidence and may not be used or disseminated in any way without prior written consent from this Company. All common law and copyright laws are hereby specifically reserved.

SIGN 2








TOWN OF NEEDHAM

DESIGN REVIEW BOARD

Public Service Administration Building 500 Dedham Avenue Needham, MA 02492 **Application and Report**

Property L	ocation: 63	Kendrick Street		Date	. 8/29/25
)wner:	EP 63 Kend	rick Realty, LLC			
ddress:	C/O Edgewat 14 Mica Lane	er Properties, LLC , Suite 202	Wellesley	MA	02481
elephone.	Street 781-552-4558	(Mitchell A. Kassler)	City	State	Zip
pplicant:	EP 63 Kend	rick Realty, LLC			
Address:	<u> </u>	ter Properties, LLC e, Suite 202	Wellesley	MA	02481
	Street 781-552-4558 (Mitchell A. Kassler)	City	State	Zip
	installer: Sign			N/A	02472
Address:	60 Arsenal S	lieet	Watertown City	MA State	02472 Zip
elephone.	. <u>617-924-029</u>	Type of Application Sign Minor Project Exterior Alterations Major Project (Site - preliminary - final Flexible Subdivision Planned Residential Residential Compou	Plan Review) Development		
-	ption of sign or ding monum	<i>project:</i> ent sign at loading and	d parking entrance to	rear parkin	g area. Si
3.75 squ	are feet in ar	ea with a total height (including base) of 4'	and is locat	ed within t
required (Ref S3)	setback and	15' from street line			

Please email completed application to elitchman@needhamma.gov



SWG

SignWorks Group

60 Arsenal Street Watertown, MA 02472 617=924=0292 fax 617=924=0279

LISTOMED

Edgewater Properties

PROJECT:

63 Kendrick

ATE:

08/25/2025

CALE:

As Noted

DRAWN BY:

ΑE

WORK ORDER:

11337

DRAWING NO

FILE:

REVISIONS:

This drawing is given in confidence and may not be used or disseminated in any way without prior written consent from this Company. All common law and copyright laws are hereby specifically reserved.

SIGN 3 SIGN 4







TOWN OF NEEDHAM


DESIGN REVIEW BOARD

Public Service Administration Building 500 Dedham Avenue Needham, MA 02492 **Application and Report**

Property 1	Location: 63 Kendrick Street		Date	e: <u>8/29/25</u>
Owner:	EP 63 Kendrick Realty, LLC			
Address:	C/O Edgewater Properties, LLC 14 Mica Lane, Suite 202	Wellesley	MA	02481
Telephone	Street 781-552-4558 (Mitchell A. Kassler)	City	State	Zip
pplicant	. EP 63 Kendrick Realty, LLC			
Address:	C/O Edgewater Properties, LLC 14 Mica Lane, Suite 202	Wellesley	MA	02481
	Street : 781-552-4558 (Mitchell A. Kassler)	City	State	Zip
ddress:	Installer: SignWorks Group 60 Arsenal Street	Watertown	MA	02472
		Watertown	MA	02472
idar ess.	Street	City	State	Zip
'elephone	.: 617-924-0292			
	Type of Application Sign Minor Project Exterior Alteration Major Project (Si - preliminary - final Flexible Subdivist Planned Resident Residential Comp	ons ite Plan Review) ion ial Development		
·	<i>iption of sign or project:</i> nding monument sign at second p	arking entrance to rea	r parking are	ea. Sign is
3.75 squ	uare feet in area with a total heigh	t (including base) of 4'	and is locat	ed within t
required (Ref S4)	setback and 15' from street line.			
· · /				









63 Kendrick Street Needham, MA

© STA Design, Inc. expressly reserves its common law copyright and other property rights in these plans. These plans are not to be reproduced, changed or copied in any form or manner whatsoever nor are they to be assigned to any third party without first obtaining the expressed written permission and consent of STA Design, Inc.



308 Congress Street, 5th Floor Boston, MA 02210 617.426.1501 www.sta-design.com

GREGORY LOMBARDI DESIGN, INC.

Landscape Architecture

221 Boston Road

North Billerica Massachusetts 01862

221 Boston Road North Billerica, Massachusetts 01862 Phone 617.492.2808





DESIGN REVIEW BOARD

No.	Description	Date
Scale		1" = 30
Project Number	-	24.050

 Project Number
 24.050

 Date
 2025.08.28

 Drawn by
 VS/WT

 Checked by
 BM


LO.0 SITE PLAN




Design Review BoardPublic Services Administration Bldg. 500 Dedham Avenue Needham, MA 02492

Application and Report

_ocation:	87 Chestnut St.	Dat	e: 09/18/25	l	
Owner:	Chestnut Dental Associates- South Shore Management LLC				
Address:	87 Chestnut St. Needham, MA 02	2492			
Street		City	State	Zip	
Telephone: _	508-801-7157				
Applicant: _	Christopher Brett Doyle				
Address:	233 Morse Rd. Sudbury, MA 0177	6			
Street		City	State	Zip	
Telephone: _	617-968-0607				
Designer/Insta	ller: LYF Architects/TD Constru	ıction			
	356 Main St. Haverhill, MA 01830				
Street		City	State	Zip	
Telephone: _	978-470-3675				
	Type of Application				
	☐ Sign☐ Minor Project				
	X Exterior Alterations				
	Major Project ☐ - preliminary				
	☐ - final				
	Flexible SubdivisionPlanned Residential	Development			
	☐ Residential Compou				
Brief descriptior	n of sign or project:				
Rework 6	existing ramp/side walk/railing in o	rder to meet ADA	A code		





LYFarchitects

SUBMISSION 9/24/25











1 2 **Design Review Board Meeting Minutes** Monday, September 8, 2025 3 7:30 p.m. 4 5 6 **Board Members:** 7 Mark Gluesing, Board Chair (P) Steve Dornbusch, Board Member (P) 8 9 Susan Opton, Board Member (P) 10 Haril Pandya, Board Member (P) 11 Felix Zemel, Board Member (P) 12 13 Elisa Litchman, Administrative Specialist, Planning & Community Development (P) 14 Mark Gluesing, Chair, called the meeting to order on September 8, 2025, at 7:30 p.m. He 15 16 reviewed the remote meeting procedures. 17 18 **Applicants & Attendees:** 19 1. Gary McCoy, Poyant Signs Inc., representing Hyannis Port Research 20 2. Joe Garber, Riverside Community Care 21 3. Walter Sullivan, Sullivan & Comerford, P.C. representing Chabad Lubavitch Jewish 22 Center 23 4. Tim Sullivan, Goulston & Storrs representing Greystar Development East, LLC 24 25 **Agenda Item 1:** 26 Gary McCoy, Poyant Signs Inc., representing Hyannis Port Research located at 400 First 27 Avenue, Needham, MA, and applying for signage. 28 29 Gary McCoy, Poyant Signs Inc., representing Hyannis Port Research, explained that the proposal 30 is for a halo-illuminated set of channel letters that will match the existing TripAdvisor sign. The 31 sign is less than 100 s.f. and will be installed on the screening system on the building. 32 33 Chair Gluesing stated that the proposed sign is not measured the way that is required by the 34 Board. Signs should be measured from the outer box around the whole limit. This sign actually 35 measures a hair over 100 s.f. Mr. McCoy stated that the way he calculated the sign in the same 36 process as was carried out for the other recent signs on this building. Mr. Zemel noted that he 37 was Chairing the meeting when the TripAdvisor sign was discussed, which may have led to the 38 acceptance of the alternate way of calculating the sign area. He agreed that the brightness level 39 and whiteness of the sign lighting should match the other signs on the building. As the other sign 40 was approved in this way, the Chair concurred. 41

Mr. Pandya agreed that the sign parameters should be confirmed. He would like to make sure the

proposed lighting matches the other signs on the building.

42

43

 Upon a motion duly made by Mr. Dornbusch and seconded by Ms. Opton, it was voted to approve the sign for Hyannis Port Research, 400 First Avenue, as submitted. Felix Zemel – aye; Haril Pandya – aye; Susan Opton – aye; Steve Dornbusch – aye; Mark Gluesing – aye; Motion passed 5-0-0.

Agenda Item 2:

Joe Garber, Riverside Community Care located at 237 Highland Avenue, Needham, MA, and applying for exterior alterations.

Joe Garber, Riverside Community Care, explained that the proposal is to complete some renovations to the front of 237 Highland Avenue. The existing elevated concrete walkway on the front of the building are crumbling and in severe deterioration. The stairs attached to the front were previously replaced with precast steps along with some railings. The proposal is to remove the elevated platform and install three separate sets of precast stairs. These will be ADA compliant for height and depth of the treads, and the handrails. Future funding for greenery along the stairs may be sought, but there is no easy way to water it. The existing bushes along the front will be removed.

Chair Gluesing expressed concern that the railings may not meet code. Mr. Garber stated that he has reviewed the proposal with the Building Inspector and did not hear any similar concerns. Mr. Zemel agreed that balusters will need to be included in the plans.

Ms. Opton suggested that decorative stone or a different landscape material could be used in place of plantings, if they would not be able to be watered. Mr. Garber stated that some mulch could be placed in between the stairs, as there is not currently a budget for any landscaping.

Mr. Pandya expressed concern with waterproofing the wall after removal of the platform. Any gaps that expose the steel beams should be waterproofed. Mr. Garber stated that these areas will be sealed.

Mr. Zemel suggested an approval with a condition that the applicant return with a shrubbery or landscape plan to be approved and implemented by next summer. In this way, the aesthetic concerns will be addressed.

Chair Gluesing stated that it is difficult to evaluate the design when it is clear that the railings will need to be changed. There will need to be code compliant railings. He expressed concern regarding finishing the lower part of the wall with veneer brick or artificial stucco. Also, mulch will need to be installed prior to the applicant coming back in the spring with a landscape plan.

Upon a motion duly made by Mr. Dornbusch and seconded by Ms. Opton, it was voted to approve the changes to the stairways at 237 Highland Avenue, Riverside Community Care, with the conditions that the lower wall and the area where the deck is removed be patched with either brick veneer or stucco and that the final product be submitted to the Board prior to installation, and that mulch be installed on the ground area and by May 30, 2026, the applicant return with a

plan for landscaping the front area. Felix Zemel – aye; Haril Pandya – aye; Susan Opton – aye; Steve Dornbusch – aye; Mark Gluesing – aye; Motion passed 5-0-0.

90 91 92

93

89

Agenda Item 3:

Walter Sullivan, Sullivan & Comerford, P.C. representing Chabad Lubavitch Jewish Center to be located at 1195 Central Avenue and applying for site plan review.

94 95 96

Mr. Zemel recused himself from this item.

97 98

99

100

Rabbi Krinsky, Chabad Lubavitch Jewish Center, stated that the Center has been in the Town for over 20 years working out of a small house on High Rock St. More space is needed for the Center's programming and celebrations to serve the community. The proposed location at 1195 Central Avenue is ideal due to its size and location.

101 102 103

104

105

106 107

108

109

110

111

112

113114

115

116 117

118

119

120

121 122

123

124125

126

127

128

129

130

Karlis Skulte, CEC, explained that the property has an existing residential home which is in a state of disrepair. The Rabbi has spoken with neighbors to obtain feedback and coordination and has spoken with the Town, including the Conservation Commission. The wetlands on the site have been delineated. There are bordering vegetated wetlands located in the southwest corner of the site. These extend adjacent to the nearby baseball fields. The associated buffer zones have been applied to the design of the project. The applicant will be working with the Conservation Commission throughout this process. The site slopes from Central Ave. towards the rear wetlands. There has been some geotechnical investigation completed to identify preliminary areas for stormwater management on the site as well as the groundwater height. The main building is proposed at the center of the site frontage, with a smaller building toward the rear. This will be the residence to serve the Rabbi and his family. There will be one-way circulation on the site, along with a few parking spaces for the congregation. The one- way drive aisle will wrap around the building. The width of the drive has been verified for a delivery vehicle. The plan includes a sidewalk connection along the entry portion of the drive. The plan shows a stormwater management basin between the existing walkway on Central Ave. and the front of the building, along with a smaller basin behind the residential home at the rear of the site. A 25' No Disturb buffer to the wetlands will be maintained and the applicant will provide additional mitigation plantings to replicate some of the wetlands that are currently grass. These areas will be revegetated into a native wetland and supplemented with additional plantings in coordination with the Conservation Commission. The plan identifies space for dumpsters in between the residence and the Center. This will be a fully fenced enclosure. There will be a 4' pond at the front of the site which would connect the runoff from the roof of the building are discharge it back to the existing wetland on the west side of the property. On the east side of the building, there will be a sloped driveway with access to the main floor of the building. This will allow for pedestrian connectivity and egress movement. The lower level of the building will have gently sloping access from the entry drive at Central Ave. to the lower level of the building. The residence will be at the same elevation approximately as the lower level of the Center. A preliminary utility plan identifies space for proposed transformers to serve the building adjacent to the entry drive along Central Ave.

131 132

Alan Westman, KSID Architecture, explained that the proposed residence will be a two story structure with an attic space creating the third floor for storage purposes. Due to high

groundwater conditions and proximity to the wetlands, it is not possible to have a basement. The residence consists of a two car garage. The Center will consist of three stories. In an effort to minimize grading and retaining walls, the building will be used for as much retaining as possible. A covered pergola is proposed on the top floor, along with an outdoor deck. A flat roof is proposed for the building. The material of the residence is proposed to be a nickel gap siding, in either a cementitious fiber cement board or a wood clapboard material. The tower piece where the stairwell is located will be a lightly textured stucco material with a large expanse of windows or curtainwall. There will be coated aluminum canopies over the garage and the front entrance, and a small deck on the residence which will be stained wood. The front of the Center is proposed to be wrapped in Jerusalem stone for the first two floors. The third floor steps back and will be a smooth textured stucco with an aluminum coated roof canopy. Along the south side of the building, materials are proposed that relate to other materials in the neighborhood, such as nickel gap siding. The two main colors being proposed for the Center are Sherwin-Williams Storm Cloud and a blue-gray color. The residence will be Origami White and the stucco above the Jerusalem stone would be matte painted to match the Jerusalem stone color. Trees will remain between the ballfield and the building. The landscape plan will work with local deciduous and evergreen trees, with plantings added to the wetland buffer and other large shrubs for screening. The final design concept for signage has not yet been considered.

Chair Gluesing asked the square footage of the Center. Mr. Westman stated that the total gross square footage is 24,880. The residence is 6453 gross s.f. The attic space will be approximately 2,400 s.f. The footprint of the residence is approximately 3,135 s.f. The entire site is 43,567 s.f.

Chair Gluesing asked the building height from grade. Mr. Westman stated that the residence is 32.5' at its tallest height above grade. The Central Ave side of the Center will be 37' high above grade at its highest point, and the back will be 42.5' above grade, as the property slopes down.

Rabbi Krinsky stated that he has spoken to the neighbor to the north who seemed in support of the project. A meeting is also planned with the other neighbors.

Mr. Pandya asked about parking for the site. Mr. Skulte explained that there were discussions with the Town and the Superintendent of Schools regarding parking at a nearby school for the site. The site has been designed for circular drop-off, with parking then at the school and access via the sidewalk on Central Ave. Rabbi Krinsky stated that there is a verbal agreement for use of the school parking area outside of school hours.

Ms. Opton asked the number of people that could be onsite during certain events. Mr. Westman stated that the social hall can accommodate approximately 120 people, and the sanctuary could accommodate approximately 100 people. Rabbi Krinsky noted that these two places are not used at the same time. People move from one area to the next. Ms. Opton asked about signage for those having to park elsewhere.

Ms. Opton noted that the landscape plan is incomplete with some of the plant species not identified and included on the plan. She would like to see a more complete plan. She asked about the proposed infiltration pond plantings. Mr. Skulte stated that this area would normally be loam and seeded. Ms. Opton suggested meadow plantings or wild marsh plantings. Chair Gluesing

stated that this would be a nice way to add softening to the short setback to the building façade.

An installation like this was done successfully at Olin College. Mr. Skulte noted that the profile of the stormwater management system is limited due to the high water table, but these proposals will be considered.

In response to a question from Mr. Dornbusch, Mr. Westman stated that there is some discussion still to be had with neighbors and abutters. He believes the applicant will have all of the necessary conversations.

Chair Gluesing stated that the property is not large enough for the two buildings proposed and there could be issues with the wetlands on the site. As the back areas is already a large lawn, he asked if building in the 25' buffer could be considered in terms of the building placement. If the applicant is proposing to not comply with other setback requirements, it is unclear why the wetland setback is being observed. Mr. Skulte stated that the wetlands consultant has met with the Town's Conservation Agent, and it seemed that the 25' No Disturb buffer needs to be preserved in order to get through the Conservation Commission process. There have been discussions with the adjacent abutter to the north to make sure that the buffering and screening needed will be feasible. Chair Gluesing stated that the elevation change on the site seems to be quite significant.

Mr. Pandya asked about outdoor gathering spaces proposed. Mr. Westman stated that there is no formal outdoor gathering space proposed, as there is not much space left. There are four smaller gathering spaces proposed within the building. Bollards, or other low lighting, is proposed around the circular drive. There will be some downlighting on the building itself. The intention is to create a lit glow from inside the building at the glazed entry hall.

Mr. Pandya stated that he believes the building is sited well and the proposed buildings feel in keeping with the area. He suggested accent lighting some of the Jerusalem stone on the building. On the upper level roof deck, the applicant could also consider some low level plantings to help screen the activities and provide privacy. Plantings and material choices may help bring the building scale down.

Chair Gluesing stated that the massing of the Center is well done, and the proposal includes elegant materials. The massing for the proposed residence seems large and he would prefer to see a smaller third floor massing. He suggested a mixing in of an alternate material on the north and west façades of the residence building. The applicant noted that it faces a wetland and is mostly not seen.

The Board stated that it would forward comments to the Planning Board.

Agenda Item 4:

222 Tim Sullivan, Goulston & Storrs representing Greystar Development East, LLC applying for 223 redevelopment of 100 West Street and site plan review.

Tim Sullivan, Goulston & Storrs representing Greystar Development East, LLC, explained that the owner of the property has an agreement with Greystar Development East, LLC to be the developer of the site for multifamily housing under the new MBTA Communities zoning. This project falls within the by-right scenario of this zoning and the Site Plan is compliant. The project includes 189 units in a three-story building, with a 1.1 floor area ratio (FAR). The project will utilize the existing curb cuts on the site. The Planning Board has been applied to and there will be a public hearing next Tuesday.

Timothy Beinert, Greystar Development East, LLC, explained that this site is across from a train station. The site has good walkability, allowing future residents to live in a suburban setting without sacrificing convenience. The design tries to maximize on the location while also fitting within the context of the greater surrounding area. The building will be a wood frame, slab on grade surface, with differentiated setbacks to create articulation and depth. There will be direct access to units on the ground floor which will create a boutique feel and activate Highland Avenue.

Tom Lassy, Cube3, stated that this property is in a multifamily residential district which has a 70% street setback frontage requirement. The proposal is for a 700' building which stretches down Highland Ave. The project is seen as a bridge between a residential area and a commercial area. The design shows angled and vertical elevation elements to break down the massing and create a residential scale feel. The materials at the West Street end will wrap the corner of the building and bays will be created to tie back onto Highland Avenue. The design is for two visual approaches to the building that meet in the middle. The bays have been angled to create vertical lines and break up the scale of the long horizontal building. At the pedestrian level there will be small canopies with vertical wood paneling to create a vertical element and break up the horizontal element. A node will be created in-between the two sections to be a bridge between the two neighborhood styles. The building will be recessed at the first floor to allow people down at the pedestrian level to be able to look inside the courtyard areas.

Mr. Sullivan explained that there is a requirement that only 30% of the building can exceed the maximum setback. The current building is a flat façade, running the whole way along Highland. The proposed façade has 30% of the building set back further with open spaces to break up the building. This was discussed during the MBTA Communities process and the Planning Board mentioned that it would like to see the entrances to the residences along the street as a way to activate the streetscape. Although the building has a long façade, there will be a lot of building design elements activating the streetscape. Mr. Beinert stated that the intention is to maximize green space for future residents.

Jay Emporer, Bohler, stated that the entry for the building on Highland Avenue will be a break between the two building masses. There will be a courtyard with seating and vegetation. There will be steps and a slightly sloped walkway to access the area. There will be light spilling out from inside the building and lighting in the landscape using bollards and downlighting of the trees. There will be movable furniture for the residents to use. Some ground floor units will open onto that space. Street trees will be located on the inner side of the sidewalk, along the building façade. The sidewalk will have continuous plantings and trees against the building. Along West Street, there will be an access point for the building and a planting strip. The plant palette is still being developed but will include a majority of native trees and perennial shrubs. There will be courtyards facing west for the residents, opening into the main amenity area of the

building. There will be a courtyard with a pergola and some dining tables. There will also be a park on the south end of the site, utilizing existing green spaces and a walking path for residents.

275 There may also be a community garden which would be fenced off.

Mr. Dornbusch asked about buffering between the south parking lot and the building. Mr. Emperor stated that there could be additional plantings included as screening. Mr. Dornbusch asked about site lighting. Mr. Emperor stated that there will be full lighting for the parking area and some accent lighting in the courtyards.

Mr. Zemel stated that there will likely be many discussions regarding this proposal at upcoming Planning Board meetings.

Ms. Opton asked about walled in garden entrances to the ground level units. Mr. Emperor stated that there will be small patios outside the doors and walkways to the public sidewalk. The area between the units will be heavily planted.

Ms. Opton noted that pin oaks may drop a lot of acorns onto the site and could be reconsidered as a planting species. There is not a lot of landscaping in the west parking area. She asked if there will be any softening of the landscape there. She noted that the ground floor units on that side seem to open directly to the parking lot with only a sidewalk buffer. Mr. Lassy stated that the entrances may be pushed in a bit to give relief at the sidewalk edge.

Ms. Opton asked about screening from the railway. Mr. Emperor stated that an existing fence there will be replaced. There may be some space for narrow tree plantings as well. Ms. Opton suggested a planter along the railway area in order to create some taller planting heights.

Ms. Opton stated that any softened angles for the building would be nice to consider.

Mr. Pandya stated that recessing some of the entry points would be appropriate. He stated that the white tone for the building color could be difficult. It would be nice to determine ways to break up the color palette. Mr. Pandya suggested that some cornice work could help to break up the homogeneity of height in the building. The applicant team agreed that this would continue to be refined.

Chair Gluesing noted that there is not much landscaping within the parking area, and he suggested clustering some of the parking in order to allow for additional screening/landscaping.

Ms. Opton suggested a planter along the railway area in order to create some planting heights.

Mr. Dornbusch asked about the unit mix. Mr. Beinert stated that there will be 16% studio units, 44% one-bedroom units, 31% two-bedroom units, and 9% three-bedroom units.

315 Mr. Pandya suggested lights coming down from the entryways, instead of sconce lights. He

316 suggested looking into heat island effects for the proposed parking area and associated

317 photovoltaic items. Mr. Lassy stated that this will be a passive house construction level project.

318	Mr. Emperor stated that the parking proposed is at a 1:1 ratio and there is not much area left to
319	minimize the impact of the parking lot.
	minimize the impact of the parking for.
320	
321	The Board stated that it would forward comments to the Planning Board.
322	
323	REVIEW
324	Minutes of 8/11/2025 minutes
325	
326	Upon a motion duly made by Mr. Zemel and seconded by Mr. Dornbusch, it was voted to
327	approve the meeting minutes of August 11, 2025. Felix Zemel – aye; Haril Pandya – aye; Susar
328	Opton – abstain; Steve Dornbusch – aye; Mark Gluesing – aye; Motion passed 4-0-1.
329	
330	Upon a motion duly made by Mr. Zemel and seconded by Mr. Dornbusch, it was voted to
331	adjourn at 10:15 p.m. Felix Zemel – aye; Haril Pandya – aye; Susan Opton – aye; Steve
332	Dornbusch – aye; Mark Gluesing – aye; Motion passed 5-0-0.
333	

Next Public Meeting – September 29, 2025 at 7:30pm